


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg, Wichita, Kansas.

SINCLAIR FRAIRIE OIL CO.
Martha Edward. No. 1.

SEC. 18 T. 16 R. 11W
NE₄ SE
330' fr N. and E. lines E₂SE₄

Total Depth. 3315 $\frac{1}{2}$
Comm. 11-8-39 Comp. 11-24-39
Shot or Treated.
Contractor.
Issued. 12-30-39

County Barton.



CASING.

Rotary 3312
Cable 3315 $\frac{1}{2}$

103/4" 110'
7" 3307'

Elevation

Production. Pot. 75 B.

Figures Indicate Bottom of Formations.

shale and shells	700
lime	730
anhydrite	740
shale and shells	1130
shale and salt	1365
shale and shells	1420
shale & lime shells	1670
shale and shells	1715
lime	1800
lime shale	1835
lime	1945
broken lime	2000
shale lime	2110
shale	2205
shale lime shells	2310
shale shells	2410
shale lime	2555
shale shells	2675
lime	2957
shale	3027
K.C. lime	3035
lime	3110
lime broken	3116
lime	3130
lime broken	3140
lime	3315 $\frac{1}{2}$
Total Depth.	

Top Arbuckle 3306

11-25-39 Temporary Swab
test made 249 bbls oil
in 5 $\frac{1}{2}$ hrs thru casing
a Temporary potential 75 B.