


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company. SINCLAIR PRAIRIE OIL CO.
Farm. Martha Edward No. 3.

SEC. 18 T. 16 R. 11 W
NW NE SE
330'fN 990'fE lines SE $\frac{1}{4}$

Total Depth. 3307
Comm. 5-11-46 Comp. 5-22-46
Shot or Treated.
Contractor. Harbar Drlg. Co.
Issued. 6-22-46

County. Barton
KANSAS



CASING:
10 3/4" 337'
7" 3304'

Elevation. _____

Production. Pot. 3000 B Max

Figures Indicate Bottom of Formations.

clay & sand stone 40
post rock 100
shale 210
shale & shells 325
shale 555
shale & shells 700
red bed 890
red bed & rock 970
sand & shells 1020
shale & shells 1225
salt 1250
shale & shells 1350
lime 1410
lime & shale 1445
shale & shells 1520
salt & shale 1550
shale sdy & shells 1565
lime brkn 1670
lime 1800
lime & shale 1890
lime 2060
shale & shells 2075
lime & shale 2175
shale 2315
shale & gyp 2470
lime & shale 2500
lime shells & shale 2605
lime & shale 2675
shale & lime brkn 2760
lime 2810
lime & shale 2864
lime hrd 2868
lime sft to med. & shale 2910
lime 2975
shale 2980
shale & lime 3045
lime brkn & shale 3090
lime hrd wh 3100
lime 3125
lime sft 3132
lime 3142
lime sft 3150
lime 3220
lime & shale 3270
lime 3307
Total Depth

Top Lansing-K.C. 3033' datum -1148'
slight oil show in top
slight show oil 3050-51
Fair porosity 3068-73 water
Good porosity - slight oil show
in top: 3125-33; 3142-50;
3171-85

Pot. 3000 bbl max.
(indicated 3572)

Tops	Surface	Rig
Brown Lime	3013	3016
Lansing-K.C.	3030	3033
Arbuckle & 7"	3301	3304
Total Depth	3304	3307