


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

SOLAR OIL CORP.
K. Schartz No. 1.

SEC. 18 T. 16 R. 11W.
SEC NE
330' EL 330' SL NE $\frac{1}{4}$

Total Depth, 3328
Comm. 8-19-39 Comp. 9-11-39
Shot or Treated. No acid.
Contractor, Springrose Drlg. Co.
Issued, 10-7-39

County Barton.



Elevation.

CASING.

12 $\frac{1}{2}$ " 192'
8 $\frac{1}{4}$ " 3318'

Production, Pot. 90 B.
Temp.

Figures Indicate Bottom of Formations.

surface clay and sand rock	25
lime shale and shells	192
red bed and shale	260
red bed	330
sand	360
shale and shells	700
lime	715
lime and iron	735
red bed and shale	780
shale	1020
shale and shells	1190
salt and red bed	1400
shale	1440
lime	1745
broken lime	1770
lime	1795
shale	1840
lime	1880
broken lime	2050
lime	2110
shale and lime	2140
shale and shells	2255
shale and lime	2335
broken lime	2405
shale and shells	2460
lime	2520
shale and shells	2620
shale	2670
broken lime	2700
lime	2857
Steel line correction 2857 equals 2864	
lime	2985 slight show oil 2872-2875
sdv shale	3020
lime K.C.	3290 cored from 3180-3192 7 $\frac{1}{2}$ Rec.
shale	3310
lime	3328
Total Depth, Halliburton Steel line.	
Top Arbuckle lime	3321.
Cored 3325-3328	2' Rec.

after standardizing cement plug was drilled and well filled to a depth
of 1575' in 17 hours.
1825' in 21 $\frac{3}{4}$ hours.
2050' in 25 $\frac{1}{2}$ hours.