


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company SOLAR OIL CORP.
Farm K. Schartz No. 7.

SEC. 18 T. 16 R. 11 W
SW NE NE
959' FEL 1086' FNL NE $\frac{1}{4}$

Total Depth. 3271 PB 3192
Comm. 4-1-46 Comp. 4-15-46
Shot or Treated. Acidized
Contractor. Mouser Drlg. Co.
issued. 7-20-46

County. Barton
KANSAS



CASING:
8 5/8" 706' Cem.
5 1/2" 3226' Cem.

Elevation. _____

Production. Pot. 687 B

Figures Indicate Bottom of Formations.

cellar	6
lime shale	55
shale shells	565
red bed	689
anhydrite gyp	698
anhydrite	707
lime	715
red bed	900
shale shells	1035
salt	1275
shale	1340
shale shells	1450
lime shale	1660
lime	1750
Florence Flint	1770
lime shale	1835
lime	1945
lime shale	2050
shale shells	2085
lime shale	2195
shale shells	2370
lime shale	2520
shale shells	2555
lime shale	2670
lime	2928
good show, good sat., good por., free oil 2829-38	
lime shale	2980
lime	3260
poor show, poor sat. sli odor 3024-30. Strong odor, good por. good sat., free oil- 3083-95. Good orod, fair por, fair sat. free oil- 3165-70.	
cherty lime	3266
quartzite	3271
Total Depth	

Perf: 58 shots 3159-74
47 shots 3077-87
35 shots 3095-3103
Acidized w/500 gals. 3159-74
w/2000 gals. 3077-3103

Plugged back 3192

Tops:
Anhydrite 698
Topeka 2645
Brown lime 2975
Kans. City 2997
Conglomerate 3259
Solid
Quartzite 3263
No Arbuckle

All Rotary Meas. to Top Kelly
Bushing 4' above Ground