


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - SOLAR OIL CORP.
Farm - Schartz No. 8

SEC. 18 T. 16 R. 11 W
SE SW NE
330' fSL & 990' fW^L of NE $\frac{1}{4}$

Total Depth. 3359' PB 3329'
Comm. 9-27-46 Comp. 10-10-46
Shot or Treated.
Contractor. Kiowa Drlg. Co.
Issued. 1-18-47

County. Barton
KANSAS



CASING:

8 5/8" 722' Cem. w/300 sx.
5 1/2" 3360.21' Cem. w/175 sx.

Elevation. _____

Production. Phy. Pot. 295 B.

Figures Indicate Bottom of Formations.

post rock	40
shells, sand & shale	240
shale & shells	540
red bed	715
anhydrite lime	790
shale & red bed	850
shale & shells	1240
salt	1300
shale & shells	1370
lime	1465
lime sdy & shale	1660
lime sdy	1695
lime hrd lgt	1740
lime & Fort Riley	1835
lime	1905
lime & shale	2045
lime sdy & shale	2200
shale & shells	2325
shale & lime	2395
lime & sdy shale	2515
shale blue	2580
lime & shale	2610
lime	2625
lime brkn	2710
lime & shale	2785
lime	2835
lime brkn	2885
lime & shale	3010
lime	3270
lime & granite wash	3285
conglomerate & granite wash	3359
Total Depth. PB 3329'	

Tops:

Anhydrite	715
Topeka	2665
Brown Lime	2994
White Lime	3012
Conglomerate	3279
Granite Wash	3356

Perf. 3286-90' (36 shots)
Perf. 3281-84' (12 shots)