


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS OIL
Farm- Hitschman "C" No. 3

SEC. 32 T. 16 R.11W
NE SE SE

Total Depth. 3320'
Comm. 6-26-57 Comp. 7-4-57
Shot or Treated.
Contractor. Bennett & Roberts Drlg.
Issued. 9-14-57

County Barton
KANSAS



CASING:
8 5/8" 301' cem w/150 sx.
5 1/2" 3319½' cem w/75 sx.

Elevation. 1870' DF

Production. 25 BOPD

Figures indicate Bottom of Formations.

clay	35
post rock	45
shale & post rock	80
sand	95
shale, shells, sandy	
red bed	283
blue shale	301
blue & gray shale &	
red bed	570
red bed & shale	735
anhydrite	764
shale & shells	1190
shale	1500
shale & lime	1750
lime	1890
lime & shale	2815
lime	2917
lime & shale	3048
lime	3320 RTD
Total Depth	

TOPS:	
Anhydrite (drillers)	735
Heebner	2927
Toronto	2944
Douglas Sand	2975
Brown Lime	3023
Lansing	3045
Base Kansas City	3285
Arbuckle	3318