


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP.
Farm - Cynthia Riemann No. 3.

SEC. 33 T. 16 R. 11 W
CW₂ SE SE

Total Depth. 3343
Comm. 3-2-46 Comp. 3-21-46
Shot or Treated. Acidized 3-20-46 w/2000 gals.
Contractor.
Issued. 5-25-46

County. Barton
KANSAS



CASING:
8 5/8" 499' LI Cem.
5 1/2" 3328' LI Cem.

Elevation. _____

Production. Pot. 387 B, no wtr

Figures Indicate Bottom of Formations.

sand rock	285
shale, shells & iron	410
shale & shells	500
red bed	725
anhydrite	770
shale & shells	780
shale, shells & red bed	920
shale, shells & salt	1075
shale & shells	1445
lime brkn	1640
shale & lime	1725
lime brkn	1890
lime	2035
lime brkn	2087
lime & shale	2205
shale & shells	2335
shale	2480
shale & shells	2580
shale & lime	2815
lime	3327
Arbuckle lime	3330
sand	3343
Total Depth	

Tops:

Hebner shale	2949
Toronto lime	2967
Douglas shale	2980
Brown lime	3047
Lansing-K.C.	3060
Arbuckle Dolo.	3327