


SHELL OIL CO., INC.
Vera O. Harzman No. 4.

SEC. 33 T. 16 R. 11W
SW SE NW
330' fSL 995' fEL NW $\frac{1}{4}$

Total Depth. 3361'
Comm. 7-27-41 Comp. 8-16-41
Shot or Treated.
Contractor.
Issued. 9-20-41

County. Barton

CASING:
8 5/8" 320' Cem.
4 1/2" 3348' Cem.



Elevation.

Figures Indicate Bottom of Formations. Production, Pot. 240 B.
No wtr, Pmpg

surface clay & limestone	30
sand & gravel	156
shale	310
red bed	326
shale	475
red rock & shale	750
anhydrite	775
shale	790
shale & shells	995
shale & lime strks	1175
shale & salt	1420
shale & lime	1800
lime brkn	1815
lime	1835
shale & lime	2722
lime	3205
3205 equals 3208 SL Corr.	
lime	3343
conglomerate, shale red & green	3347
dolomite SIM	3349
dolomite	3361
Total Depth.	

Top Arbuckle dolo. 3347

fair porosity & slight
stain 3080-86
good porosity 3156-91
good porosity & sat. 3319-27
225' oil $3\frac{3}{4}$ hrs 3358
slight porosity & sat. 3353-58
swb 202 oil, 15 wtr 11 hrs
swb 141 oil 12 wtr 7 hrs 3361

Acidized 2000 Gals. Acid 3358
Acidized 4000 Gals. Acid 3358