

SHELL OIL CO., INC.
V. O. Harzman No. 5.

SEC. 33 T. 16 R. 11 W
NE SW NW
993'f SL 995'f WL NW $\frac{1}{4}$

Total Depth. 3356'
Comm. 10-16-41 Comp. 11-5-41
Shot or Treated.
Contractor.
Issued. 11-29-41

Rotary O-3354
Cable 3354-56

County. Barton



CASING:
8 5/8" 394' Cem.
4 1/2" 3352' Cem.

Elevation.

Production. Pot. 2811 B. Echo.

Figures Indicate Bottom of Formations. Drawdown, No wtr

surface clay	35
sand, gravel, shale	150
shale & lime	255
sand & clay	386
lime	394
red rock & shale	766
anhydrite	790
shale & lime strks	1210
salt & shale	1433
lime & shale	2685
lime	2890
shale & lime	2937
lime	2987
shale & lime	3052
lime (3353-54 SLC)	3351
dolomite	3356
Total Depth.	

Top Arbuckle dolomite
3351 SL Corr.

11-2-41 acidized 2000 Gals.
from 3352-56
11-4-41 acidized 2000 Gals.
from 3352-56

3196-3204 excellent poro.,
no oil stain
3351-54 good porosity,
scattered oil stain w/
some dead stain
3354-56 good porosity,
good oil staining thruout
2125' oil 5 hrs, 2555' oil
in 5 1/2 hrs, 2725' oil in
6 hrs, 2905' oil 7 1/2 hrs