


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

Company - SINCLAIR-PRAIRIE OIL CO.
Farm - Hargman No. 3.

SEC. 33 T. 16 R. 11 W
SE SW SE
330' FEL 330' FSL W/2 SE $\frac{1}{2}$

Total Depth. 3358
Comm. 3-14-46 Comp. 4-1-46
Shot or Treated.
Contractor. Harbar Drlg.
Issued. 6-22-46

County. Barton
KANSAS



CASING:
10 3/4" 310'
7" 3356'

Elevation. _____

Production. Est. 25 B

Figures Indicate Bottom of Formations.

surface soils	60	Bottom collar - ground level	6'	0
sand	120	Ground Level - Derrick Floor	2'	
shale	200	Derrick Floor - Top Rotary		
sand	260	Bushing	2'	
shale & shells	550			
red bed	625			
shale red	725			
anhydrite	750			
shale & shells	1170			
salt	1330			
shale & shells	1430			
lime & shale	1450			
lime	1565			
lime brkn	1650			
lime	1720			
lime & shale	1805			
lime	1885			
lime cherty	1890			
lime	2040			
lime & shale	2060			
lime	2195			
lime & shale	2370			
shale	2400			
lime & shale	2575			
lime brkn	2600			
lime sdy	2620			
lime brkn	2670			
lime & shale	2740			
lime	3015			
shale-lime-brkn	3035			
lime & shale	3060			
lime	3130			
lime cherty	3150			
lime	3310			
lime-conglomerate	3358			
Total Depth				

Tops :	Rig	Surface
Lansing K.C.	3063	3061
Conglomerate	3326	3324
Arbuckle & 7"	3356	3354
Total Depth	3358	3356

2968-80 thin oil stain, no odor
3048 top brown lime
3063 top Lan-K.C.
sli porosity - no show:
3073-78; 3090-03;
3063-67; 3173-82.
3233-38 sli stain & odor.
slight porosity
3243-45 sli. porosity,
sli stain, strong odor.
3258-63 sli porosity, sli.
stain, no odor
3308-13 sli por., sli stain,
no odor