

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY ALEDO OIL & GAS CO. & MURFIN DRILLING CO.

SEC. 34 T. 16 R. 11W
LOC. SW SE NW

FARM Frees

NO. 1

TOTAL DEPTH 3389

COMM. 1-24-51


COMP. 2-6-51

SHOT OR TREATED

CONTRACTOR Murfin Drilling Co.

ISSUED 4-7-51

COUNTY Barton
KANSAS



CASING

8 1/4" 224' cem. w/150 sx

5 3/16" 3368' cem. w/75 sx

ELEVATION 1924 D.F.

PRODUCTION 2399 BOPD plus 14%
water

FIGURES INDICATE BOTTOM OF FORMATIONS

sand, shale & shells	200
sand	212
shale & shells	224
shale	400
redbed	600
redbed & shale	755
Anhydrite	782
redbed & shells	1190
salt & shale	1345
shale & lime	1766
sand	1780
shale & lime	1825
lime	1930
shale & lime	2395
shale	2520
lime & shale	2920
lime	2955
lime & shale	3100
lime	3310
lime & shale	3389
Total depth	

Tops; Derrick Floor

Topeka	2713
Heebner	2968
Dodge	2986
Brown lime	3071
Lansing	3091
Cherty Conglomerate	3355
Arbuckle	3367
Rotary T. D.	3386