


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - THE EL DORADO REFINING CO.
Farm - Frees "A" No. 7

SEC. 34 T. 16 R. 11W
SW NE NE

Total Depth. 3376
Comm. 7-17-50 Comp. 7-27-50
Shot or Treated.
Contractor. Sterling Drlg. . .
Issued. 9-2-50

County. Barton
KANSAS



Elevation. 1942 DF

CASING:
8 5/8" 320' cem w/150 sx.
5 1/2" OD 3375.74' cem w/80 sx.

Production. Draw down 2914 BOPD
no water

Figures Indicate Bottom of Formations.

clay, shale, shells	318
shale, shells	750
anhyd.	755
shale, shells, salt	1390
shale, shells	1440
shale, lime	1640
lime	2155
lime, shale	2715
lime	2995
lime, shale	3090
lime RTD	3373
lime arbuckle	3376
Total depth	

Tops:
Heebner 2987
Dodge 3003
Br. Lansing 3088
Lansing 3104
Arbuckle 3370
no conglomerate

RTD 3373, fair odor, good-fair porosity
good SFO. Drld. shoe, fluid kicked tools
up hole. Had 1400' OIH/40 mins thru bridge.
DD to 3374 T.D. 2950' OIH/3 hrs. \$ 166.68
BO/3 hrs, 1600' O.B.