


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
508 E. Murdock, Wichita, Kansas

Company - THE ELDORADO REFINING CO.
Farm - Frees "A" No. 8

SEC. 34 T. 16 R. 11W
SW SW NE

Total Depth. 3410 RB
Comm. 7-29-50 Comp. 8-8-50
Shot or Treated.
Contractor. Sterling Dr. lg.
Issued. 9-2-50

County. Barton
KANSAS



Elevation. 1938 DF

Production. dry

CASING:

8 5/8" 320' cem w/150 sx.
5 1/2" OD 3309' cem w/100 sx.

Figures Indicate Bottom of Formations.

surface clay, shale, shells 318
shale, shells 755
anhyd. 775
shale, shells 1200
salt, shale, shells 1435
lime, shale 1550
lime 2200
lime, shale 2675
lime 2985
lime, shale 3085
lime 3372
cong. 3398
arbuckle lime 3410
Total depth R.B.

Tops: DF
Heebner 2985
Dodge 2997
Br. lansing 3077
Lansing 3098
Conglomerate 3371
Arbuckle 3397

CO to T.D. 3408, DF ran Gamm-Ray
soft 3268-74
Perf. (12) 3268-72, NS.
(6) 3272-74 NS
(6) 3266-68, some sat. fossiliferous
lime in gun parts. 500 acid @ 900# broke to
300# and fed.
FU 5 GO and 250' wtr o'nite.
∅ 30 gals s. water and scum dead oil pr hr for
2 hrs.
Perf. (22) 3005-09 DF
1000 acid, 350' fluid o'nite, 30' very heavy oil,
test 1 bblr fluid pr hr, 5% oil bal salt water.