

WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
Wichita, Kansas

Company - THE EL DORADO REFINING CO., et al
Farm - Breford No. 2

SEC. 36 T. 16S R. 11W
SE NW NE

Total Depth. 3365
Comm. 8-12-49 Comp. 9-3-49
Shot or Treated. 10 qts. nitro. 1000 gals. acid
Contractor. Sterling Drlg. Co.
Issued. 11-19-49

County. Barton
KANSAS



CASING:
8" set @ 284' w/150 sx
5" set @ 3378.48' w/100 sx.

Elevation. _____

Production. 53 BOPD & 70% wtr.

Figures Indicate Bottom of Formations.

Rock, clay & shale	160
Shale & shells	685
Anhydrite	715
Shale & shells	1040
Shale, shells & salt	1400
Shale & lime	1590
Broken lime	1730
Lime	2040
Shale & lime	2320
Shale	2435
Shale & lime	2670
Lime	2910
Broken Lime & shale	2985
Shale & lime	3020
Lime	3340
Conglomerate	3350
Lime	3355
Lime	3365

Cable Tool Total Depth

FORMATION TOPS D.F.

Heebner sh.	2917
Lansing	3034
Ch. Congl.	3333
Arbuckle dol.	3351

Shot w/10 qts. nitro. T.D.
Acid. 500.
Lane-Wells Gamma-Ray plug @ 3250
Perf. (18) 3223-29
Acid. 500 gals.