


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

J.J. LYNN
A.F. Smith Estate No. 1.

SEC. 36 T. 16 R. 11 W.
CS $\frac{1}{2}$ NE SW

Total Depth. 3373
Comm. 1-22-42 Comp. 2-13-42
Shot or Treated.
Contractor. H.M. Williams
Issued. 4-25-42

County Barton.



CASING.

10" 260' cemented.
5 $\frac{1}{2}$ " 3350' cemented.

Elevation.

Production. Pot. 367 B.

Figures Indicate Bottom of Formations.

soil	10	
shale	33	
shells	38	
chalky lime	40	
lime shells	235	
shale and shells	600	
shale and pyrites of iron	710	
shale and shells	1040	
red bed and shale and shells	1160	
salt, shale and shells	1375	
shale and shells	1435	
broken lime	1545	
broken lime and hard shale	1630	
shale	1682	
lime and shale breaks	1695	
shale and lime	1770	
broken shale and lime	1860	
lime and shale	1873	
blk sticky shale	1895	
cherty lime	1905	
broken lime	2095	
lime shell and shale	2105	
broken lime and shale	2244	
shale and shells	2470	
lime and shale	2540	
shale	2625	
broken lime	2732	
lime and hard shale	2800	
shale blk and shell	2812	
lime and shale	2844	
lime	2890	
lime and shale breaks	2925	
broken lime	2995	
broken lime and shale	3038	
Kansas City lime	3065	
lime and shale	3090	show of oil 3076
porous lime	3093	show of oil 3095
lime	3123	
lime hard	3135	
lime soft good show oil	3138	show of oil at 3138
lime	3141	
lime Cored	3143'6"	
lime	3153	
lime Porous	3160	Porous lime with show oil 3152-3181
lime	3240	
lime porous	3255	show of oil 3240-3255
lime and shale breaks	3335	
broken lime	3340	
conglomerate	3352	
Arbuckle lime	3373	
Total Depth.	1st show oil 3360	
	Filled up 1200'	

Top Kansas City lime 3038