

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

Company SINCLAIR PRAIRIE OIL CO.  
Farm Joe Prusa No. 5.

SEC. 20 T. 16 R. 11 W  
NE SE NE  
330' fE 990' fSL NE  $\frac{1}{2}$

Total Depth. 3370 PB 3240 Surface Level Meas.  
Comm. 11-2-45 Comp. 11-19-45  
Shot or Treated.  
Contractor. Harbar Drlg. Co.  
issued. 1-12-46

County. Barton  
KANSAS



CASING:  
10 3/4" 320' Cem.  
5 1/2" 3359' Cem.

Elevation. ....

Production. Pot. Swab 43 BO,  
104 BW

Figures Indicate Bottom of Formations.

surface soils	60
shale & shells	210
sand	230
shale & shells-Reamed to 13 1/4" hole	330
shells	345
sand	385
shale & red bed	730
anhydrite	760
shale & shells	1070
shale	1420
lime	1780
lime shale & shells	1855
lime	1925
shale	1940
lime	2000
lime & shale	2055
shale & shells	2530
shale & lime	2590
shale	2625
lime	3105
lime sft	3113
lime med	3130
lime sft	3145
lime	3205
lime sft	3220
lime med	3225
lime	3325
chat rough	3335
cherty dolomite	3345
cherty lime	3370
Total Depth	

Run Schlumberger  
Soft & porous 3105-10 no show  
Very faint oilstain 3125-30  
Very sft, very faint oil stain 3130-44  
Soft & porous 3170-75  
Faint oil stain 3205-15  
Plugged back to 3240 Surface level meas.

Tops:	Rig Floor-Surface Level	
Lansing-Kans. City	3025	3022
Conglomerate	3303	3300
Arbuckle	3357	3354

5 1/2" set at (150 sx) 3359 3356  
Total Depth 3370 3367  
Perf. 20 shots 3203-10 Acid 1000 gal  
5 gals water, rainbow oil  
Perf: 11 shots 3168-72  
12 shots 3172-76 Acid 1000 gal  
24 hrs swbd 43 BO, 104 BW  
Minimum 25 Bbl daily