

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

Company - ANDERSON-PRICHARD OIL CORP.
Farm - Soyfert No. 5

SEC. 21 T. 16 R. 11W
CS $\frac{1}{2}$ N $\frac{1}{2}$ SE

Total Depth. 3389'
Comm. 2-15-49 Comp. 3-25-49
Sector Treated. Shot 20 qts. 3383-89
Contractor. Transit Corporation
Issued. 4-30-49

County. Barton
KANSAS



Elevation. _____

Production. Phy. Pot. 31 BOPD &
55% water

CASING:

8-5/8" 277' Cem. W/200 Sx.
5-1/2" 3366' Cem. W/150 Sx.

Figures Indicate Bottom of Formations.

surface clay & rock	110
sand, shale & shells	165
shale	575
red bed & shale	745
anhydrite	775
shale & shells	1425
shale & lime	1880
lime	2135
lime & shale	2910
lime	3280
lime cherty	3315
lime	3365
lime & chert	3375
lime?	3389
Total Depth	

Tops:

Anhydrite	760
Lansing	3073
Conglomerate	3352
Arbuckle	3364

15 GOPH: Shot 20 qts. 3383-89
Swab. 25 BO & 25 BW, 24 hrs.