


WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SINCLAIR PRAIRIE OIL CO.
Farm - Martha Laudick No. 2

SEC. 21 T. 16 R. 11 W
NW NE NW
330' fNL 330' fWL NE $\frac{1}{4}$ NW $\frac{1}{4}$

Total Depth. 3276 $\frac{1}{2}$ '
Comm. 1-18-45 Comp. 1-31-45
Shot or Treated. 1000 gals.
Contractor. Harbar Drlg. Co.
Issued. 4-14-45

County. Barton
KANSAS



Elevation. _____

Production. Pot. 2166 BO,
no wtr

CASING:

9 5/8" 365' Cem.
5 1/2" 3275' Cem.

Figures Indicate Bottom of Formations.

surface clay & sand rock	40
shale & shells	365
shale, shells & red bed	695
shale & shells	1250
shale, shells & salt	1350
shale & shells	1730
lime & iron	1790
lime	1905
lime brkn	1960
lime	2040
lime & shale	2160
lime brkn	2250
shale & shells	2420
lime brkn	2480
lime & shale	2720
lime	3276 $\frac{1}{2}$
Total Depth.	

(Derrick Floor Meas.)

Tops:
K. C. Brown lime 2975
Lansing-K.C. 2990
Arbuckle 3260 $\frac{1}{2}$
TD 3267 $\frac{1}{2}$

5 1/2" set at 3275

Best oil show 3270-75

3-8-45 on draw down test made

Pot. 2166 BO, no wtr
after perforating and
acidizing w/1000 gals.

Perf. 6 shots 3258-63
24 shots 3264-66