


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
Farm- Kraft No. 1

SEC. 26 T. 16 R. 11W
SE NW NW

Total Depth. 3390'
Comm. 4-23-59 Comp. 5-1-59
Shot or Treated.
Contractor. Shields Drlg. Co.
Issued. 7-18-59

County Barton
KANSAS



CASING:

8 5/8" 330' cem w/210 sx.

Elevation. 1921' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale, shells & sand	330
shale & shells	737
Anhydrite	766
shale & shells	1235
shale & lime	1815
broken lime	1945
lime & shale	2125
shale & shells	2545
shale & lime	2790
lime	2905
lime & shale	3150
lime	3165
lime & shale	3235
lime	3375
Conglomerate	3390 RTD
Total Depth	

TOPS:

Anhydrite (scout)	737
Heebner	2960
Toronto	2980
Douglas Shale (scout)	2992
Brown Lime	3056
Lansing-Kansas City	3072
Sh. Conglomerate	3354
Ch. Conglomerate	3363

DST #1 3133-60', op 1 hr, w/very weak
blow for 8 min. Rec. 10' rotary mud.
BHP 898#/20 min.