

WOLF CREEK OIL COMPANY.
 Kraft No. 1.

SEC. 26 T. 16 R. 11W.
 SWc SW


46553

Total Depth, 3420.
 Comm. 2-23-35 Comp. 4-30-35
 Shot or Treated.
 Contractor.
 Issued, 5-4-35.

County, Barton.

CASING.

15 1/2" 480' 8 1/2" 2821 lowered to 3000
 12 1/2" 735' lowered to 3095
 lowered to 758 6" 3385'
 10" 2072'



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

clay yellow	40	lime	2005	lime	3134
slate blue	105	lime and shale	2020	shale	3139
mud blue	150	lime	2035	lime	3145
shale white	240	shale	2045	slate and shells	3160
sand	250	lime	2050	lime	3230
red rock	265	red rock	2060	slate	3235
slate blue	275	lime	2085	lime	3295
red sand	310	shale	2090	shale	3300
sand	345	lime	2125	lime sdy	3310
red rock	355	shale	2135	lime	3325
slate blue	365	red rock	2145	slate	3330
shale blue	425	shale blue	2170	lime	3365
slate blue	440	lime	2175	conglomerate	3378-
sand	460	shale and shells	2215	(questionable on account of	
slate blue	480	lime	2230	drilling 10 ft at one run)	
sdv shale	490	shale	2240	lime	3397
slate blue	530	lime	2250	siliceous lime	3415
red rock	540	shale	2260	White siliceous lime	3420
shale red	580	lime	2270	Total Depth.	
slate red	650	slate & shells	2290		
shale red	670	shale blue	2310		
lime	675	shale and shells	2330		
slate red	695	shale	2350		
red rock	750	lime	2355		
anhydrite lime	765	shale	2380		
lime	780	slate and shells	2425		
red rock	830	lime	2445		
red rock	985	shale	2480		
slate	1055	slate	2490		
slate brown	1075	lime	2515		
shale blue	1155	lime	2530		
slate blue	1195	shale	2545		
salt and shale	1205	lime	2565		
salt	1425	slate	2570		
shale grey	1435	lime	2580		
slate and shells	1480	slate and shells	2595		
lime	1500	lime	2605		
shale blue	1510	shale blue	2640		
lime	1545	lime	2650		
slate and shells	1595	shale	2655		
lime	1605	lime	2695		
shale blue	1630	slate and shells	2710		
lime	1635	lime	2750		
shale and shells	1670	lime sdy	2770		
red rock	1690	lime	2840		
lime	1710	shale	2845		
slate and shells	1725	lime	2870		
lime	1745	shale	2880		
lime	1760	lime	2980		
sand grey soft	1775	shale	2985		
lime	1810	lime	2995		
lime broken	1825	shale	3000		
lime	1835	lime	3005		
slate and shells	1845	slate	3010		
lime	1865	red rock	3015		
shale	1875	slate and shells	3025		
red rock	1880	shale	3058		
lime	1945	lime	3070		
shale	1955	shale and shells	3090		
lime	1970	lime soft	3105		
shale brown	1975				

WATER RECORD

1 BW at 240-250
 5 BW 275-285
 HFW 285-290
 HFW 485
 1 BW 1760-1780
 2 BW 1810-1825
 2 BW 2755-2770
 3 BW 2885
 1 BW 3300-3310
 T.D. hole full sulphur wtr.
 small show gas at 1690
 showing of oil 3335
 show of oil 3396.