


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - GULF OIL CORP. & HINKLE OIL CO.
Farm - Willenberg No. 2.

SEC. 27 T. 16 R. 11 W
SW SE NW

Total Depth. 3387
Comm. 2-4-45 Comp. 2-25-45
Shot or Treated.
Contractor. Hinkle Oil Co.
Issued. 5-12-45

County. Barton
KANSAS



CASING:
10" 105'
5" 3383'

Elevation. _____

Production. Pot. 22 $\frac{1}{2}$ B

Figures Indicate Bottom of Formations.

clay & gravel	34
lime & shale	105
shale	290
sand	365
shale & shells	1065
shale & salt	1225
shale & shells	1310
shale	1445
shale & lime	1705
shale	1730
lime	1765
sand	1775
lime	2015
shale & lime	2368
lime	2464
lime & shale	2755
lime	2975
lime & shale	3077
lime	3330
lime & shale	3361
lime	3387
Total Depth	

Tops:

K. C. 3089
Conglomerate 3362
Arbuckle Dolo. 3382

Cem. w/100 sacks of cement
Filled w/oil 1250' in 2 $\frac{1}{2}$ hrs.
Temp. prod. 25 BPD allowable.
Swbd 75 Bbls. in 3 hrs. 1000' from bottom.