


BARNSDALL OIL CO.
Anna Rous No. 2.

SEC. 28 T. 16 R. 11W
CSL NE SW

Total Depth. 3346'
Comm. 1-2-40 Comp. 1-20-40
Shot or Treated.
Contractor. Parker Drilg. Co.
Issued. 2-3-40

County. Barton



CASING:
10 $\frac{3}{4}$ " 155'9" DF
5 $\frac{1}{2}$ " 3342' DF

Elevation.

Production. Pot. 183-B.

Figures Indicate Bottom of Formations, no wtr, 9 hrs pumping test

cellar	11
sand & gravel	21
shale & lime shells	160
shale & shells	485
shale & red bed	760
anhydrite	798
shale & shells	1220
salt	1275
shale & salt	1395
shale & shells	1485
shale & sand	1500
shale & shells	1660
shale & lime	1770
sand	1780
sand brkn	1790
shale	1823
lime	1850
lime brkn	1925
lime	1975
lime brkn	2010
shale & lime shells	2205
lime brkn	2220
shale & lime shells	2304
shale & shells	2500
lime brkn	2555
shale & shells	2641
lime brkn	2695
lime	2910
shale & lime	2931
lime brkn	2998
lime brkn & shale	3065
lime	3070
shale & lime	3090
lime	3170
lime brkn	3340
cored lime	3346
Total Depth, Derrick floor	

*Production Pot: 59,084 B.
Depthograph Maximum
3000 Bbls.*

Gore Records:
3340-46 rec 3 $\frac{1}{2}$ '
2" shale, 1' lime
2'4" Arbuckle dolomite

Top Arbuckle 3344' rotary
table, 3343' Derrick floor

1-22- 66 BO, 0 wtr 5 hrs
pumping test before acid
1-23- 183 BO, 0 wtr 9 hrs
pumping test after acid