

BARNSDALL OIL CO.
Anna Rous No. 4.

SEC. 28 T.16 R.11W
CEL NW SW

Total Depth. 3388'
Comm. 4-23-40 Comp. 5-3-40
Shot or Treated.
Contractor. Parker Drlg. Co.
Issued. 6-22-40

County. Barton



CASING:
10 $\frac{3}{4}$ " 180'7"

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

limestone & clay	40
sandstone	47
shale & lime shells	185
shale, shells, red bed	590
shale & red bed	772
anhydrite	798
shale & shells	1225
salt	1395
shale & lime shells	1550
shale & brkn lime	1705
shale & shells	1768
sand	1780
shale & shells	1810
sand	1820
lime	1840
shale & sdy lime	1885
shale & lime	1955
shale & brkn lime	2125
shale & shells	2495
lime brkn	2560
shale & shells	2570
lime brkn	2755
sand	2765
lime	2973
shale & lime	3064
lime brkn	3085
lime	3230
shale & lime	3240
lime	3275
shale & lime	3345
cored	3355
cored	3367
conglomerate	3372
shale & conglomerate	3376
conglomerate	3382
cored	3388
Total Depth.	

Core Record:

3345-55 rec 8'
3' shale & congl.
5' lime w/shale strks
3355-67 rec 10'
5' lime, 1' shale, 4' congl.
3382-88 rec 2' congl. w/chert,
small pieces of weathered dol.
1st 2" sdy