


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.

B. B. & M. DRILLING CO.
Esfeld No. 6

SEC. 28 T. 16 R. 11 W.
SW SE SE

Total Depth. 3396
Comm. 11-17-41 Comp. 12-29-41
Shot or Treated.
Contractor.
Issued. 8-8-42

County Barton.



CASING.

13 $\frac{1}{2}$ " 445'
10" 765'
8 $\frac{1}{4}$ " 1990'
UR 2459'
7" 3190'
5 $\frac{1}{2}$ " 3353'

Elevation.

Production. Pot. 1662 B.
plus 21 $\frac{1}{2}$ Wtr

Figures Indicate Bottom of Formations.

cellar	10	shale	2175	3362 equals 59	
yellow clay	40	lime	2190	lime	3369
shale	150	shale	2215	shale	3379
shale sdy	160	lime	2225	conglomerate	3394
shale	195	shale	2235	shale	3395
shale red	235	lime broken	2250	lime	3396
shale	275	shale	2270	Total Depth.	
sand	365	lime	2285		
shale	475	shale	2305	Top Anhydrite	759
sand	490	lime	2310	Arbuckle	3359
shale	533	shale	2325		
red rock	605	lime	2330		
shale red	759	shale	2335	HFW	290
anhydrite	790	lime	2355	3 BWPH	475-90
shale red	815	red rock	2365	1 BW	1800
red rock	860	shale	2375	1 $\frac{1}{2}$ BWPH	1840-50
shale red	990	lime	2385	1 BWPH	2400-15
shale	1050	red rock	2390	$\frac{1}{2}$ BWPH	2480-90
red rock	1100	shale	2400	1 BW	3145
shale	1170	sdv shale	2420	Water	3220
salt	1180	shale blk	2430	4 BWPH	3220-30
shale	1190	shale	2455		
salt	1440	lime	2460	slight sh oil	3320-30
shale and shells	1470	shale	2465	show oil	3359
shale	1490	lime	2470	1/2 BOPE	3395-96
lime	1520	shale	2480		
shale and shells	1575	shale sdy	2515		
lime	1580	lime	2540		
shale	1590	shale	2545		
lime	1610	lime	2550		
shale	1615	shale and shells	2570		
lime	1620	shale	2575		
shale	1640	lime	2590		
lime	1685	shale	2595		
lime broken	1695	lime	2610		
red rock	1700	shale	2665		
lime	1840	lime	2670		
sand	1850	shale	2675		
lime	1875	lime	2685		
shale	1885	shale	2700		
lime	1890	lime	2725		
lime shells	1940	shale	2730		
shale blk	1950	lime	2855		
shale & shells	1965	shale	2860		
lime	1975	lime	2990		
shale	1980	shale	3008		
lime	1985	lime	3025		
shale	1990	red rock	3035		
lime	2000	shale	3092		
shale	2015	lime	3180		
red rock	2020	shale	3185		
lime	2030	lime	3225		
shale lime shells	2055	sdv lime	3230		
red rock	2060	lime	3260		
lime	2090	red rock	3265		
red rock	2100	lime	3355		
lime	2155	lime & shale	3362		