

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND OIL & GAS CO.
Farm E.F. Esfeld No. 2.

SEC. 28 T. 16 R 11 W
SE NE NE
330' NSL 330' NEL NE NE

Total Depth. 3367
Comm. 10-31-45 Comp. 11-3-45
Shot or Treated.
Contractor.
issued. 1-5-46

County. Barton
KANSAS



CASING:
8 5/8" 262'5" Cem.
5 1/2" 3353'4" Cem.

Elevation. _____

Production. Pot. 170 B

Figures Indicate Bottom of Formations.

surface clay & limestone	0-125
lime & shale	216
chay & limestone	440
shale sticky	622
shale & red bed	740
anhydrite	770
shale & shells	1230
salt & shale	1485
shale & shell	1625
lime brkn	1780
lime sdy	1810
shale & lime	1900
lime brkn	1955
lime & shale	2142
lime brkn	2255
shale	2485
shale & shells	2713
lime	2970
lime & shale	3062
lime	3074
shale	3076
lime	3287
shale & lime	3331
dolomite	3339
lime & shale	3343
shale	3348
lime brkn & shale	3363
dolomite	3367
Total Depth	

5 1/2" csg set @ 3333'
w/150 sacks.
Landed 2 1/2" tbg @ 3343'

Pumping test:
56.78 BO, no wtr, 8 hrs.
Pot. 170 BO

Tops:
Lansing 3060
Arbuckle 3330