

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANGLIND OIL & GAS COMPANY
Farm - E. Esfeld No. 5

SEC. 28 T. 16 R. 11W
CS/2 NW NE
990' SN1 1980' WE1 NE/4

Total Depth. 3301'

Comm. 2-25-47


Comp. 3-13-47

Shot or Treated.

Contractor.

Issued. 4-12-47

County. Barton
KANSAS



CASING:

8-5/8" 733' Cem. w/325 sx
5-1/2" 3296' Cem. w/150 sx

Elevation. _____

Production. Pot. 3000 bbls.

Figures Indicate Bottom of Formations.

shale & shells	0-205
shale & red bed	320
red bed sdy	465
shale & red bed	724
anhydrite	750
red bed & shale	900
shale & shells	1550
shale & lime	1620
lime	1700
shale & lime	1775
lime hrd	1800
lime & shale	1835
lime	1940
lime brkn	2035
lime hrd	2085
shale & lime	2190
shale brkn	2265
shale	2395
shale & lime	2630
shale	2662
lime	2685
shale & lime	2935
lime	2960
shale	3005
lime	3061
shale & lime	3090
lime	3301
Total Depth	

Swab test: 7 hr. swab test
9 BOPH, no water

Tops:

Lansing 3026

Arbuckle 3296-3301

ended 2 1/2" tbg. @ 3261'