

WELL LOG BUREAU -- KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - STANOLIND O & G CO.

Farm - E. Esfeld

No. 7

SEC. 28 T. 16 R. 11 W

NE SW NE

1650' SNL & 1650' WEL NE $\frac{1}{4}$

Total Depth. 3337'

Comm. 4-7-47

Comp. 5-1-47


Shot or Treated.

Contractor.

Issued. 8-16-47

County. Barton

KANSAS



CASING:

8 5/8"

744' Cem. w/300 sx.

5 1/2"

3330' Cem. w/150 sx.

Elevation. _____

Production, 96 BO, no wtr.
8 hr. swab test.

Figures Indicate Bottom of Formations.

clay & rock	0-40
shale & shells	540
red bed & shale	736
anhydrite	765
red pan	875
red bed & shale	900
shale & shells	1125
shale	1170
shale & salt	1375
shale & shells	1440
Ft. Riley	1470
shale sticky	1485
Ft. Riley	1505
lime hrd	1530
lime & shale	1615
lime brkn	1665
lime & shale	1750
lime	1815
lime brkn	1943
lime & shale	1975
lime brkn	2030
limo & shale	2045
limo	2105
limo & shale	2410
shale & shells	2450
lime & shale	3047
K. C. limo	3095
limo	3337
Total Depth.	

Tops:

Lansing 3047

Arbuckle 3331-3337

Landed 2 1/2" tbg. @ 3320'