


WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company - SINCLAIR OIL & GAS CO.
Farm - Community-Selma No. 10
Seyfert

SEC. 29 T. 16 R. 11W
C1/4 N7 NE
375' fm W 625' N

Total Depth. 3286
Comm. 4-16-50 Comp. 4-30-50
Shot or Treated.
Contractor. Kiowa Drilling Co.
Issued. 8-5-50

County. Barton
KANSAS



CASING:
10 3/4" 335' cem w/200 sx.
7" 3278' cem w/150 sx.

Elevation. 1866 DF

Production. Pot. 514 oil, 10%
wtr.

Figures Indicate Bottom of Formations.

Post rock	35
shale, shells	245
sand	320
shale, shells	335
shale, red bed,	695
shells	
red bed, shells	705
anhydrite	750
red bed, shale	860
shale, shells	1215
salt, shale	1285
shale, shells	1485
lime, shale	1785
sandy lime, shale	1815
shale, lime, sand	1900
shale, lime shells	2080
shale, shells	2125
lime, shale	2175
shale, shells	2295
shale	2405
lime, broken	2500
shale, lime	2705
lime	2940
sand, shale, lime	2995
gray lime, shale	3015
lime	3080
lime, hard	3085
lime-soft, medium	3135
lime-hard	3140
lime	3286
Total Depth	

Tops: Schlumberger

Topeka	2652
Topeka Chert	2668
Heebner 2888	2896
Douglas 2940	2925
Lan-KC 3007	3012
Arb. Lime 3278	3277

Swabbed 16 hrs made 210 oil, 15%
wtr. 5-8-50 state tes, pumping
Potential 514 oil, 10% wtr.

Corrected to Surface Level.