

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

508 East Murdock

Wichita, Kansas

Company - SPRINGER INTERESTS et al  
Farm - South Oeser No. 7

SEC. 30 T. 16 S. 11W  
NW SW ST

Total Depth. 3292

Comm. 10-18-50

Shot or Treated.

Contractor.

Issued. 9-15-51

Comp. 11-15-50

County. Barton

KANSAS



Elevation. 1913 DF

Production. 107 BO & NW

CASING:

8 5/8" 314'  
5 1/2" 3160'

Figures Indicate Bottom of Formations.

no log from 0 to	2600	shale gry w/streaks
shale gry	2605	lime 3121
dolomite gry	2609	xyn lime cream 3126
shale pyrite gry	2616	cream oolitic & oolitic-
lime cream to gry	2628	astic lime stain, sat.
shale gry	2642	& odor 3132
gry micro xln lime		cream oolitic & oolitic-
fussulina	2646	astic lime wtr 3150
lime & shale gry		xln lime gry to brn 3166
mottled	2675	shale blk 3169
xln lime	2700	xln & oolitic lime,
xln lime	2715	sli stain 3174
lime porous, oolitic		xln lime 3180
in part	2730	shale gry w/streaks
chert	2735	tan & cream lime 3201
xln lime	2745	xln lime, tan to brn,
lime fossiliferous,		blk tight oolitics 3226
plant stems & fussulina	2750	shale blk 3230
		xln lime gry to brn 3253
xln lime	2771	shale gry 3259
shale blk carbonaceous	2774	fractured quartzite,
xln lime	2790	slight stain & odor 3272 RTD
shale	2800	fractured quartzite 3284
micro xln lime	2826	l BOPD
shale gry	2829	quartzite 3292
xln lime gry & brown	2840	Total Depth
shale blk	2844	
brown lime sli. oolitic,		Tops:
tight no odor or stain		Anhydrite 752
circ. 1 hr.	2856	Topeka 2672
lime gry	2866	Shawnee Pay 2874-2883
shale gry	2870	Heebner 2928
oolitic lime, porous,		Levenworth Lime 2932
some vuglar & stained.		Snyderville Shale 2936
sli. odor, circ. 1 hr	2883	Dodge or Toronto 2943
lime gry tight	2886	Douglas Shale 2954
lime gry fair odor in		Douglas Sand 2972-2987
samples	2890	Brown Lime 3022
xln lime micro	2928	Lansing-K.C. Lime 3036
heebner shale blk		Weathered Quartzite 3257
carbonaceous	2932	
xln lime coarse	2936	DST: 2972-2985' packer
shale gry	2943	set 2972. Open 1 hr.
oolitic lime porous	2959	circ. 2 hrs. fair stain
red & gry shale	2973	& odor. Gas 12 min. good
gry mica, silty sand.	2988	blow. rec. 35' gas cut
shale red & gry	3021	mud.
brown coarse xln lime,		
no stain or odor	3029	
shale gry & red	3041	
oolitic lime, slight		
stain	3056	
shale gry	3066	
oolitic lime, sli stain		
& odor	3077	
shale drk gry	3081	
xln lime gry	3096	
shale gry	3099	
brown oolitic lime	3102	