


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock Wichita, Kansas

Company - THE SPRINGER INTERESTS
Farm - South Oeser No. 8

SEC. 30 T. 16 R. 11W
SW NW SW

Total Depth. 3263½ PB 3180
Comm. 10-25-50 Comp. 11-29-50
Shot or Treated.
Contractor.
Issued. 9-15-51

County. Barton
KANSAS



Elevation. 1916 DF

Production. 118 BO & MW

CASING:

8 5/8" 320'
5 1/2" 3257'

Figures Indicate Bottom of Formations.

no log from 0 to	2600		
xln lime	2606	xln lime brown	
shale gry	2611	coarse	3163
lime gry	2624	shale blk	3168
shale gry	2638	xln lime cream fine	3192
xln lime gry	2646	oolitic lime, porous	
shale w/lime streaks	2679	vuglar, goo sat.	3197
xln lime	2696	xln lime micro	3232
shale gry	2705	shale blk	3235
lime gry to cream	2725	xln lime micro	3246
chert w/streaks wht	2730	shale blk	3254
sln lime	2745	quartzite, small	
xln lime, fussulina	2766	show oil	3263½
shale blk	2769	Total Depth	
xln lime	2773		
shale gry	2779	Tops:	
lime cream to gry	2785	Anhydrite	750
shale gry	2796	Topeka	2679
xln lime cream	2821	Shawnee Pay	2870-2880
shale gry	2826	Heebner	2923
lime gry to cream	2838	Levenworth Lime	2926
shale blk	2839	Sniderville Shale	2930
xln lime coarse gry	2862	Dodge or Toronto	2938
shale gry	2866	Douglas Shale	2956
porous lime sli oolitic, sli stain fair odor, circ. 1 hr. 2875.	2874	Douglas Sand	2968
shale gry	2879	Brown Lime	3016
porous lime, sli stain fair odor	2890	Lansing-K.C.	3034
xln lime gry to tan	2923	Quartzite	3254
heebner shale	2926		
xln lime coarse gry	2930	DST: 3123-3130, Tool open 1 hr. Gas 12 mins. rec. 1700' clean oil, no water.	
shale gry	2938	Perforated 36 holes, 3119-3126, swabbed 4 bbls. per hr.	
cream oolitic to tight lime, no stain or odor	2956		
shale red & gry	2968		
gry mica silty sand, no stain or odor	2983	Rotary to 3257'.	
gry mica, silty sandy shale	2994		
shale red & gry	3019		
xln lime, brown, no stain or odor	3027		
shale gry & red	3038		
xln to oolitic lime, porous to tight, sli stain and odor	3050		
xln lime cream to gry oolitic & ooliticastic lime, some good staining and sat., fair odor	3072		
shale gry	3077		
lime gry drk oolitics, tight	3092		
shale gry	3102		
lime gry to cream	3110		
xln lime cream	3123		
cream oolitic & ooliticastic lime, good stain, sat. and odor	3150		