


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- BENNETT & ROBERTS OIL
 Farm- Hitschman "C" No. 1

SEC. 32 T. 16 R. 11W
 NE NE SE

Total Depth. 3350'
 Comm. 3-17-57 Comp. 3-27-57
 Shot or Treated.
 Contractor. Bennett & Roberts Drlg.
 Issued. 6-14-58

County Barton
 KANSAS



Elevation. 1875' DF

Production. 30 BOPD

CASING:
 10 3/4" 305' cem w/175 sx.
 7" 3342' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface soil & clay	30
shale	60
sand	65
shale	85
sand	95
shale, sand rock	170
red bed & shale	275
blue shale	323
blue & gray shale	550
red bed & shale	760
Anhydrite	765
shells & shale	1315
shale & lime streaks	1335
lime & shale	2050
shale	2530
shale & lime	2975
lime	3350 RTD
Total Depth	

TOPS: MEAS. R.B.
 Cimmerron Anhydrite 760 (Driller)
 Heebner Shale 2932
 Toronto Lime 2950
 Douglas 2962
 Brown Lime 3032
 Lansing-Kansas City 3054
 Basal Kansas City 3300
 Arbuckle 3341

no electric log run.

DST #1 Sun Formation Testers: single
 2958-3020' packer, 62' anchor. Tool open 1 hr,
 weak blow 60 mins, rec. 85' muddy
 water with no show, BHP in 30 mins,
 935# .., FFP 150#.

DST #2 Sun Formation Testers: single packet,
 3341-50' 9' anchor, tool open 1 hr, fair steady
 blow 60 mins, rec. 510' froggy oil,
 gassy w/210' gas on top of test.
 BHP in 20 mins, 965#, IFP 100#,
 FFP 270#.