

4-16-11W ✓

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


Company- ROBINOWITZ OIL CO.  
Farm- Foster No. 1

SEC. 4 T. 16 R. 11W  
N/2 N/2 NW

Total Depth. 3249'  
Comm. 3-29-63 Comp. 4-6-63  
Shot or Treated.  
Contractor. Sholom Drig. Co., Inc.  
Issued. 7-13-63

County Barton

KANSAS



Elevation. 1769' KB

CASING:

8 5/8" 252' cem w/160 sx.

Production. DRY

Figures Indicate Bottom of Formations.

clay, rock & shale	60
shale	252
shale & shells	320
dry Dakota & pyrite	620
anhydrite	650
shale & shells	1135
shale & sand	1400
sand & lime	1465
lime & shale	1775
lime	1870
lime & shale	1910
shale & shells	2090
shale & lime	2380
sandy shale w/lime streaks	2535
shale & lime	2660
lime & shale	2755
lime	2781
lime & shale	2835
shale & lime	2890
lime	3116
lime & shale & conglomerate	3204
conglomerate	3240
lime	3249 RTD
Total Depth	

TOPS:

Anhydrite	620
Topeka	2552
Heebner	2798
Toronto	2813
Douglas	2828
Lansing	2887
Base Kansas City	3136
Conglomerate	3214

DST #1 2735-2781' Rec. 150' watery mud.

DST #2 2805-2950' Rec. 1050' VHGCN,  
120' VSOCN.

DST #3 2960-3000' Rec. 330' watery mud.