

15-009-21252

State Geological Survey
WICHITA, KANSAS


KANSAS DRILLERS LOG

S. 5 T. 16S R. 11W ^E_W

Loc. C W/2 NE NE

County Barton

640 Acres
N



Locate well correctly

Elev.: Gr. 1796

DF 1799 KB 1801

API No. 15 — 009 — 21,353
County Number

Operator
Hummon Oil Company

Address
400 One Main Place, Wichita, Ks 67202

Well No. #1 Lease Name Foster

Footage Location
790' feet from (N) (S) line 990' feet from (E) (W) line

Principal Contractor Allen Drilling Co. Geologist Byron E. Hummon, Jr.

Spud Date 10-8-77 Total Depth 3280 P.B.T.D. 3245

Date Completed 10-14-77 Oil Purchaser Koch

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8	28#	275'	Common	175 sx.	2% gel 3% cc
Production		5 1/2"	14#	3275'	Pozmix	100 sx.	18% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			Open hole		3175-81
TUBING RECORD					
Size	Setting depth	Packer set at			
2"	3179				


ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil 10 bbls.	Gas MCF	Water 10 bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval(s) 3175-81	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Hummon Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: oil	
Well No. #1	Lease Name Foster		
S 5 T 16S R 11W E W			
WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
DST #1 2831-2985 OP 45-45-45-45 BHP 852-743 Weak blow throughout FP 110-140 Rec. 100' M w/ spots of oil BHT 101			LOG TOPS Anhyd. 657 +1144 B. Anhyd. 687 +1114 Heebner 2834 -1033 Brown Lime 2927 -1126 Lansing 2942 -1141 B. K.C. 3211 -1410 Arbuckle 3271 -1470 LTD 3280
DST #2 3210-80 OP 45-45-45-45 Good Blow throughout BHP 969-925 Rec. 140' O&GCM FP 88-303 60' HOCM BHT 104 120' VHOCM 120' MO 180' SMO			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Signature Wilber D. Berg Title 12-11-79 Date		

216515