

6-16-114

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- ICER ADDIS
Farm- Woydziak

No. 1

SEC. 6 T. 16 R. 11W
C W/2 SE SW

Total Depth. 3319'

Comm. 2-21-62


Comp. 3-3-62

Shot or Treated.

Contractor. Sholom Drlg. Co.

Issued. 7-7-62

County Barton
KANSAS



CASING:

8 5/8" 527' cem w/300 sx.
5 1/2" 3314½' cem w/125 sx.

Elevation. 1860' KB

Production. 77 BOPD, NW

Figures indicate Bottom of Formations.

clay	10
post rock	70
shale	130
shale & clay	350
sand	410
hard sand	414
sand & shale	428
hard sand & pyrite	447
shale & hard sand strks.	507
Plug & cement	527
red bed	745
Anhydrite	768
shale & shells	1400
lime & shale	2660
lime	3309
Arbuckle dolomite	3319 RTD
Total Depth	

TOPS:

Anhydrite	745-768
Heebner	2914
Toronto	2933
Lansing	3022
Arbuckle	3305

DST #1 3183-3210', Rec. 420' gas + 60' HOCM & 70' Wtr.

DST #2 3283-3309', Rec. 20' mud + 20' oil.

DST #3 3305-3314', Rec. 10' oil + 30' mud.

DST #4 3304-3319', Rec. 480' oil.