

8-16-11W<sup>P1</sup>

DRILLER'S WELL LOG

DATE COMMENCED: February 21, 1984  
DATE COMPLETED: February 27, 1984

The Roxana Corporation  
WIRTH B-2  
NE NE SW  
Sec. 8, T16S, R11W  
Barton County, Ks.

ELEVATION: 1926 K.B.

0 - 690' Surface Soil, Post Rock, Clay  
690 - 715' Anhydrite  
715 - 2880' Shale & Lime  
2880 - 2884' Shale  
2884 - 2897' Lime & Shale  
2897 - 2908' Lime  
2908 - 2971' Shale  
2971 - 2986' Lime & Shale  
2986 - 3262' Lime  
3262 - 3324' Shale, Lime Chert, Sand  
3324 - 3330' Dolomite  
3330' RTD

FORMATION DATA

Anhydrite 690'  
Heebner 2880'  
Toronto 2897'  
Douglas 2908'  
Br. Lime 2971'  
Lansing 2986'  
Base K.C. 3262'  
Conglomerate 3288'  
Arbuckle 3324'  
RTD 3330'

Surface Pipe: Set new 8-5/8"  
23# pipe @368' w/200 sacks  
60/40 pozmix 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Ervin Neighbors*

Subscribed and sworn to before me this 30 day of February 1984.

My Comm. Expires:

4-29-86

*Dorothy M Hague*  
Notary Public

