

17-16-11W
N/2 N/2 SW

DRILLER'S LOG

LOUIS KAHAN
M. Oeser #7
N/2 N/2 SW
Sec. 17-16S-11W
Barton Co., Ks.

Commenced: 1-11-80
Completed: 1-16-80

Surface Casing: 515' of 8-5/8"
cemented w/300 sx common, 2% gel,
3% cc. 1-12-80

FORMATION

DEPTH

Surface Hole	0 - 523
Shale & Red Bed	523 - 780
Shale & Lime	780 - 1980
Lime & Shale	1980 - 2890
Lime	2890 - 3305 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess
Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 17th day of January, 1980.

Dorothy L. Schmidt
Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1983

M. Oeser No. 7
Day Work

17-16-11W

1-14-80	2nd Tour	Circ for samples @ 2960	45 min
		Circ for samples @ 3000	45 "
		Circ for samples @ 3060	30 "
	3rd Tour	Circ for samples @ 3090	45 "
		Circ for samples @ 3110	45 "
1-15	1st Tour	Circ for samples @ 3140	45 "
		Circ for samples @ 3180	45 "
		Circ for samples @ 3205	45 "
	2nd Tour	Circ for samples @ 3230	45 "
		Circ for samples @ 3270	45 "
		Circ for samples @ 3290	15 "
	3rd Tour	Circ for samples @ 3290	15 "
		Circ for samples @ 3105	2 hrs
		Pulled 7 stands & back to bottom	40 "
Circ for log @ 3305		1 hr 20 "	
	One-half trip to log	2 hrs 30 "	
1-16	1st Tour	Wait on loggers	45 "
		Logging	4 hrs 15 "
		Pipe to bottom	2 hrs 15 "
		Circ to condition hole	45 "
	2nd Tour	Circ to condition hole	15 "
			<hr/>
			22 hrs 30 min