

17-16-11W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg. Topeka, Kansas

Company HARRY GORE
Farm Oeser

No. 1


SEC. 17 T. 16 S11W
C1N1 SE NW

Total Depth: 3196' PB 3079'
Casing 3-11-42
Start of Cement 11-11-50

DEEPENING RECORD

Comp. 4-11-42

County: Barton
KANSAS



1873 (m)

Elevation 1875

Production Pot. 306 bbls

CASING

12-1/2" 450' P 5-1/2" liner 160' 9" Cem. w/30 sx
10-3/4" 746' P
8-1/4" 2440' P
7-1/2" 3071' Cem. w/75 sx

Figures indicate Bottom of Formations.

cellar	0-10	lime brkn	2060
lime & clay	30	lime	2070
shale blue	185	slate blue	2080
sand water	190	lime	2085
shale wh	220	red rock	2092
red rock	225	lime	2115
shale wh	235	shale & shells	2140
red rock	255	lime	2165
shale blue	265	slate	2170
red rock	270	shale & shells	2190
shale blue	288	lime	2200
red rock	293	shale & shells	2260
shale blue	300	shale brwn	2265
red rock	312	lime	2275
shale blue	325	shale & shells	2325
slate	390	shale blue	2330
sand water	400	lime	2340
shale blue	450	shale blue	2345
slate & iron	455	shale & shells	2395
sandwater	465	shale blue	2405
shale blue	515	lime	2410
red rock	735	shale sdy	2425
gyp	736	shale blue	2436
lime anhydrite	758	lime	2442
red rock	960	shale blue	2445
shale blue	1005	lime	2455
red rock	1060	lt shale	2460
slate	1145	shale & shells	2610
salt	1380	lime	2620
shale & shells	1450	shale & shells	2650
lime	1485	lime	2797
shale blue	1490	shale blue	2804
shale & shells	1520	lime	2897
red rock	1525	slate	2900
shale & shells	1635	shale blue	2912
red rock	1645	lime Dodge	2928
lime	1675	shale blue	2938
shale blue	1685	red rock	2940
lime	1795	sft lime	2955
red rock	1800	lime	2965
lime	1830	shale & shells	3000
shale blue	1835	red rock	3005
lime	1855	shale	3007
shale blue	1860	lime K.C.	3055
lime	1870	shale blue	3058
red rock	1880	shale & lime shells	3065
lime	1905	lime	3070
red rock	1910	shale blue	3072
shale & shells	1935	lime, gas & oil	3079
scale blue	1945	November 27, 1947	
lime	1950	Began drilling	
shale blue	1960	lime	3148
lime	2000	shale	3150
red rock	2009	lime	3189
lime	2030	lime hrd	3193
shale sdy	2035	lime Oil Pay	3196

Water Record:

2 BW	185-190
15 BW	390-400
HFV	455-465
2 BW	1725-1735
2 BW	1760-1775
2 BW	2410-2425
1 1/2 BW	2685-2695
Water	2940-2955

Initial Production: 306 BO
on retake potential June 25,
1942.

1991 BO - Depthograph.

Small show og gas 1550
S.O. 2835-2845
Gas 2915
Gas 3010
S.O. 3193-3196

Plugged back to 3079 and
is producing from this pay,
the plug has not been drilled
out.

1-28-48 Prod.- 60 bbls oil
/ 10-wtr

Total epth
Plugged back to 3079