

WICHITA BRANCH

KANSAS DRILLERS LOG


API No. 15 — 009 — 21,272
 County Number

S. 17 T. 16 R. 11
 Loc. C S2 S2 SE

Operator
 S & K Oil Co.

County Barton

Address
 Box 559 Tulsa, Oklahoma 74101



Well No. #6 Lease Name E. Oeser

Footage Location 330' FSL 1320' FWL
 feet from (X) (S) line feet from (E) (W) line

Elev.: Gr. 1811

Principal Contractor DNB Drilling, Inc. Geologist R. B. Gebhart, Jr.

Spud Date 3/27/77 Total Depth 3340 P.B.T.D. 3266 B.P.

Date Completed 5/15/78 Oil Purchaser NCRA

DF 1813 KB 1816

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	32	597	Common	300	2% Gel 3% CaCl
Production	7-7/8"	5-1/2"	14	3339	Common	225	2% Gel 3% CaCl

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
--	--	--	4	Jef	3245-51
TUBING RECORD			4	Jef	3270-76
Size	Setting depth	Packer set at	4	Jef	3299-03
2-1/2	3250	--			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 Gal. 15% Acid, 1000 Gal. 28% Acid	3245-51

INITIAL PRODUCTION

Date of first production 5/15/78	Producing method (flowing, pumping, gas lift, etc.) Pumping		
RATE OF PRODUCTION PER 24 HOURS	Oil 21 bbls.	Gas T. S. T. M. MCF	Water 2 bbls.
Disposition of gas (vented, used on lease or sold) Used on Lease.		Producing interval (s) 3245-51	
		Gas-oil ratio -- CFPB	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator S & K Oil Co. 515810
DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. 6 Lease Name E. Oeser Oil

S 17 T 16 R 11 ~~W~~

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	605		
Shale	605	669		
Anhydrite	669	691		
Shale	691	1375		
Lime & Shale	1375	1785		
Shale	1785	1980		
Lime & Shale	1980	3255		
Lime	3255	3340 TD		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>P. D. Brown</i>
	Signature
	Petr. Engr.
	Title
	6/19/78
	Date

DRILLERS' LOG

S & K OIL COMPANY
No. 1 E. Oeser 'A' # 6 E Oeser per c c
C S/2 S/2 SE/4 Sec. 17-16S-11W
Barton County, Kansas

Commenced: 11-7-77
Completed: 11-11-77

Surface Casing: 597.35' of 8-5/8"
cemented w/300 sx common, 2% gel, 3% cc
11-7-77

FORMATION

DEPTH

Surface Hole	0 - 605
Shale	605 - 669
Anhydrite	669 - 691
Shale	691 - 1375
Lime & Shale	1375 - 1785
Shale	1785 - 1980
Lime & Shale	1980 - 3255
Lime	3255 - 3340 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 11th day of November, 1977.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979