

KANSAS DRILLERS LOG

S. 17 T. 16 R. 11 ^K/_W

API No. 15 — 009 — 21,514
County Number

Loc. 280' S/ SE NW SE

County Barton

Operator

Louis Kahan

Address

P. O. Box 559 Tulsa, Oklahoma 74101

Well No. #7

Lease Name
E. Oeser

Footage Location

1370 feet from (N) (S) line 1650 feet from (E) (W) line

Principal Contractor

DNB Drilling, Inc.

Geologist

R. Gebhart

Spud Date

11-6-78

Total Depth

3390

P.B.T.D.

3304


Date Completed

12-3-78

Oil Purchaser

Koch

640 Acres
N



Locate well correctly

Elev.: Gr. 1841

DF 1843 KB 1846

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	32	474	Common	275	2% Gel 3% c.c.
Production	7 7/8"	5 1/2"	15.5	3309	Common	200	2% Gel. 3% c.c.

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement
----	----	----

PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
4	Jet	3268-78

TUBING RECORD

Size	Setting depth	Packer set at
2 1/2	3250	----

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gal. of 15%	3268-78

INITIAL PRODUCTION

Date of first production 12/5/78		Producing method (flowing, pumping, gas lift, etc.) Pump			
RATE OF PRODUCTION PER 24 HOURS	Oil 20	Gas T.S.T.M. MCF	Water 0	Gas-oil ratio ----	CFPB
Disposition of gas (vented, used on lease or sold) Used on lease.			Producing interval(s) 3268-78		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **Louis Kahan** DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No. **7** Lease Name **E. Oeser** **Oil**

S17 T16 R11 EW

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	-0-	482		
Red Bed	482	694		
Anhydrite	694	718		
Shale & Lime	718	1245		
Shale	1245	1690		
Shale & Lime	1690	1990		
Lime & Shale	1990	3010		
Lime	3010	3390	RTD	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

<p>Date Received</p>	<p><i>A D Brown</i></p> <hr/> <p>Signature</p> <hr/> <p>Petroleum Engineer</p> <hr/> <p>Title</p> <hr/> <p>1/19/79</p> <hr/> <p>Date</p>
----------------------	--

088519

DRILLER'S LOG

Kakan

S & K OIL COMPANY
No. 7 E. Oeser
280' S of SE NW SE
Sec. 17-16S-11W
Barton Co., Ks.

Commenced: 11-6-78
Completed: 11-12-78

Surface Casing: 474' of 8-5/8"
cmtd w/275 sx common, 2% gel, 3% cc.
11-7-78

FORMATION

DEPTH

Surface Hole	0 - 482
Red Bed	482 - 694
Anhydrite	694 - 718
Shale & Lime	718 - 1245
Shale	1245 - 1690
Shale & Lime	1690 - 1990
Lime & Shale	1990 - 3010
Lime	3010 - 3390 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

Ella Priess

Ella Priess

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 13th day of November, 1978.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp. April 30, 1979

515885

State Geological Survey
WICHITA BRANCH

DRILLER'S LOG

S & W OIL COMPANY
No. 1 E. Street
2201 S. of 31st St
Sec. 17-100-11W
Barton Co., Kas.

Commenced: 11-6-71
Completed: 11-12-71

Surface casing: 714' of 8-5/8"
and 714' of 6-3/4" at 11-12-71

FORMATION

Surface
Red bed
Sandstone
Shale & lime
Shale
Shale & lime
lime & shale
lime

482
601
718 - 1242
1242 - 1243
1243 - 1244
1244 - 1245
1245 - 1246

I do hereby certify that the foregoing statements are true and correct
to the best of my knowledge and belief.

J. H. R. DRILLING, INC.

Elio Priano

Elio Priano

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 14th day of November, 1971.

Dorothy L. Schmidt

Dorothy L. Schmidt, Notary Public

Notary Public Seal