

20-16-11W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SINGLAIR PRAIRIE OIL CO.
Farm Peter Schmitt No. 6.

SEC. 20 T. 16 R. 11 W
SW SE NW
990' FEL 330' FSL NW 1/4

Total Depth. 3393 PB 3350 DF
Comm. 2-18-46 Comp. 3-9-46
Shot or Treated. 1000 gals. acid
Contractor. Harbar Drlg.
Issued. 5-25-46

County. Barton
KANSAS



CASING:
10 3/4" 409'
5 1/2" 3393' DF

Elevation. 1879' sh

Production. Pump. Pot. 125 B plus
2% Wtr.

Figures Indicate Bottom of Formations.

surface soil 70
shale & shells 335
sand 400
shale 500
shale & shells 600
red bed 730
anhydrite 780
shale & shells 1430
shale & lime 1535
shale & shells 1560
lime 1970
lime brkn 2040
shale 2145
shale & shells 2235
shale 2325
shale & lime 2435
lime 2975
lime brkn 3010
shale 3025
lime 3105
lime & shale 3120
lime 3317
sand-show oil 3322
shale 3326
sand-show oil 3334
Top Cherty
Conglomerate 3340
sand 3375-3379
lime-Arbuckle
sli oil show 3393
Total Depth

very soft 3120-55
odor gas & faint
oil stain in top
(carries wtr)
sli oil show 3260-65
Conglomerate 3317
Cherty Conglomerate 3340
Arbuckle 3379

Sand 3317-22 show oil
shale 3322-26
Sand 3326-34 show oil
Sand 3375-79 show oil
Production from perforations 3315-20

Plugged Back 3350 DF

Tops - DF
Douglas Sand 2968
Lansing 3038
sli oil show in top
sli oil show 3060-65
sli oil show 3075-80
sli oil show 3085-90