

**KANSAS DRILLERS LOG**

API No. 15 — 009 — 21,474  
County Number

S. 21 T. 16 R. 11 <sup>W</sup>  
Loc. C SE NW NW  
County Barton

Operator  
Louis Kahan

Address  
P. O. Box 559 Tulsa, Ok 74101


Well No. #6 Lease Name Laudick

Footage Location  
990 feet from  (N)  (W) line 990 feet from  (N)  (W) line

Principal Contractor DNB Drilling, Inc. Geologist Mr. R. Gebhart

Spud Date 10/21/78 Total Depth 33 P.B.T.D.

Date Completed 12/1/78 Oil Purchaser KOCH



Elev.: Gr. 1886  
DF 1888 KB 1891

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surf.	12 1/4"	8 5/8	32#	604	Common	300	3% Gel 2% CC
Prod.	7 7/8"	5	15.5	3315	Common	150	3% Gel 2% CC

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
---	---	---	4	Jet	3170-74
TUBING RECORD			4	Jet	3205-12
Size	Setting depth	Packer set at	4	Jet	3257-63
2 1/2"	3200	---			

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated
2000 Gal. 15% & 28% Acid	3170-74
	3205-12
	3257-63

**INITIAL PRODUCTION**

Date of first production 12/1/78 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil <u>10</u> bbls.	Gas <u>T.S.T.M. MCF</u> bbls.	Water <u>0</u> bbls.	Gas-oil ratio <u>---</u> CFPB
---------------------------------	---------------------	-------------------------------	----------------------	-------------------------------

Disposition of gas (vented, used on lease or sold) Vented Producing interval (s) 3170-63

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Louis Kahan DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 6 Lease Name Laudick Oil

S 21 T 16 R 11 E W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface Hole	0	604		
Shale	604	734		
Anhydrite	734	756		
Shale & Lime	756	1975		
Lime & Shale	1975	3030		
Lime	3030	3317	RTD	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>A. D. Brown</i>
	Signature
	Petroleum Engineer
	Title
	1/18/79
	Date