

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

505 East Murdock,

Wichita, Kansas


21-16-11W

Company- DUKE DRILLING CO.
Farm- Perdue No. 3

SEC. 21 T. 16 R. 11W
200' E of NW SW NW

Total Depth. 3336'
Comm. 2-22-61 Comp. 3-2-61
Shot or Treated.
Contractor. Duke Drlg.
Issued. 6-10-61

County Barton
KANSAS



CASING:
8 5/8" 321' cem w/225 sx.
5 1/2" 3335' cem w/275 sx.

Elevation. 1902' KB

Production. 35 BOPD

Figures indicate Bottom of Formations.

surface clay & post rock	60
shale	80
sand	92
shale	130
shale & sand	320
shale	360
shale & sand	550
red beds	748
Anhydrite	775
shale & shells	1435
shale & lime	1880
lime	2175
lime & shale	2670
lime	2928
shale Heebner	2932
lime & shale	2946
lime Toronto	2958
shale - Douglas	3023
lime - shale - Iatan	3042
lime Lansing	3319
dolomite Arbuckle	3336 RTD
Total Depth	

TOPS:

Anhydrite	748
Heebner	2928
Toronto	2946
Iatan	3023
Lansing	3042
Arbuckle	3319