


27-16-11W

HINKLE OIL CO. & GULF OIL CORP.
Willenberg No. 1.

SEC. 27 T. 16 R. 11W
CSL SW NW
660' E WL 330' N SL NW $\frac{1}{4}$

Total Depth. 3367'
Comm. 4-4-40 Comp. 4-19-40
Shot or Treated.
Contractor.
Issued. 5-25-40

County! Barton



CASING:
10 " 97'
5 $\frac{1}{2}$ " 3358'

Elevation.

Production. Pot. 2984 B.

Figures Indicate Bottom of Formations.

shale	490
lime	600
shale & shells	640
sand	680
red rock	747
shale & shells	751
lime	775
shale & shells	1143
salt	1325
shale	1530
lime	1685
lime brkn & lime	1940
shale	1952
lime	2026
shale	2090
lime brkn & shale	2440
shale	2493
lime	2671
shale blk	2710
sand	2718
lime	3170
shale	3200
lime	3358
Arbuckle	3367
Total Depth.	

3100' of fillup in 6 hrs