

April 1943

Solar. # 1 Schartz
Sec. 18-16s-11w, SE NE
Elev. 1883'

Rotary to 3328' equals 3318'

Pennsylvanian conglomerate 3308'-3313'

3308-3313 Sandy lime. Buff to pink limestone with included sand grains. Some loose fresh cherts, in part quartzose and oolitic from the Cotter in basal part are probably detrital pebbles in the limestone. Marine cong.

Arbuckle Top 3313' Penetration 15' Subsea -1430'
3313-3318 Dolomite, white, coarsely crystalline, porous and oilstained. Post Boyce.
3318-3328 Dolomite as above. Cable tool samples almost worthless due to abundance of caving Penn shale.

Remarks: Small producer.