

Solar, # 2 Schartz  
Sec. 18-16s-11w, ~~24~~ ~~24~~ ~~24~~ CSL SW NE Rotary ✓  
Elev. 1842'

Pennsylvanian conglomerate None.

Pre Cambrian Top 3250' Penetration 33½' Subsea -1408'  
~~3250-3270~~ Quartzite, white, coarsely granular with large  
light colored micas--clear to very light  
green.  
3270-3283½ Clayey quartzite. Large quartz grains and a few  
books of light colored mica in a matrix of  
pale greenish clay. Probably an arkosic  
sand altered to an arkosic quartzite by low  
grade metamorphism and then subjected to  
prolonged weathering on the Pre Cambrian  
surface during which the feldspars weathered  
to clay.

Remarks: Test abandoned with no encouraging shows of oil.

Solar, # 3 Schartz ✓  
Sec. 18-16s-11w, ~~24~~ ~~24~~ ~~24~~ CSL SW NE Rotary