

August 1944

Sinclair #2 Edwards  
Section 18-169-11W, C SE SE  
Elev. 1894'

Rotary

Pennsylvanian Conglomerate 3327'- 3340'

3327-3340 Chert conglomerate. Cotter cherts oxidized bright red, yellow, etc. Not much worn. Rare fragments show limestone contacts.

Pre-Pennsylvanian land wash Top 3340'

Subsea -1446'

3340-3350 Chert and clay. Oxidized unworn Cotter cherts showing red clay contacts. Some sandy red and white clay.

3350-3398 Samples poor to worthless. Some sandy red clay. Chert and sand are rare to absent. Impossible to tell what was drilled in this interval. Probably Post Boyce residual clays.

Arbuckle Top 3398' Penetration 7'

Subsea -1504'

3398-3405 Sandy dolomite. White, medium and coarsely crystalline dolomites with included medium and coarse sand grains. Half a dozen chips in uncirculated rotary samples. Pre Cotter, Boyce member.

Remarks: Dry hole.

RFW:HL