

✓  
Sincliar, # 2 Peter Schmidt  
Sec. 20-16s-11w, SW NW  
Elev. 1881' ~~DF~~ ~~u.~~ ~~P~~

April 1943

Pennsylvanian conglomerate

None. Clean light buff limestone cover.

Arbuckle Top 3321' Penetration 12' Subsea -1440'

3321-3333 One sample only--circulation at 3333' TD.

Dolomite, white, coarsely crystalline with a few included sand grains. Excellent porosity and some light brown oilstain. Post Boyce.

Top from Cole, Letter # 12, 1940 who states that a core was taken from 3322' to 3324' with full recovery of white dolomite showing a few spots of saturation and in which the lower 6" indicated water with good porosity.

Remarks: Dry hole.

This test ~~XXXXXXXXXX~~ shows that the water level in the Post Boyce dolomite reservoir is near -1440'.

RFW