

Feb. 1943

✓
Sinclair, # 1 Dolechek (Joseph J.)
Sec. 32-16s-11w, CWL NW NW
Elev. 1913'

Rotary

Pennsylvanian conglomerate 3330'-3353'

3330-3351 Limestone with included sand grains and
quartzite fragments. Some well rounded
quartzite pebbles in limestone at base.
3351-3353 Loose sand and rare fragments of Cotter chert.
Marine conglomerate.

Arbuckle Top 3353' Penetration 15' Subsea -1440'

3353-3361 Dolomite, white, medium and coarsely
crystalline with some included sand grains.
Post Boyce.
3361-3368 No samples.

Remarks: Dry hole.

RFW