

April 1943

Sinclair, # 1 Anton Rodetzke
Sec. 16-16s-11w, SW/c
Elev. 1881'

Rotary to 3310' equals 3308' corr.

Pennsylvanian conglomerate

None. Clean buff limestone cover.

Arbuckle Top 3306' Penetration 8½' Subsea -1425'

3306-3309 Dolomite, white, coarsely crystalline, oil stained.
Post Boyce.

3309-3312½ Dolomite as above but with 5% included fine sand.
Porosity is considerably impaired by the presence
of about 5% light green clay.

Remarks: No structural estimate on an Arbuckle datum can be made.

Test made a 151 bbl. well. An additional few feet of penetration
should considerably improve this figure.

RFW