

WEST PHILLIPS PROSPECT (1964)

State Kansas County Barton

Company Messman-Rinehart Oil Co. Well No. 1

Farm Ehrlich


Survey _____

Block No. _____ Sec. 11 Twp. 16 S Range 13 W

Co-Ord. _____ Elev. 1913' KB
1911' B/F

SW SE NE

M-R Rig



50% - A. A. Seeligson, Jr.
25% - Chicago Group
25% - Messman-Rinehart Oil Co.

ORI - Chas. H. Wallace

3400' Arbuckle test to be
comm. by 6/1/64

NOTE: Show Sketch of Lease and Well Location in Above Space

Ft. from N. Line 330

Ft. from S. Line _____

Ft. from W. Line 660

Ft. from E. Line _____

Date	Depth	
5/26/64		M.I.R.T.- Spud - 8-5/8" @ 291
		w/155 sx. cem., 3 gel., 3 c.c.
		P.D. @ 6:10 a.m. 5/27/64
5/28	885	Drlg.
	875	Anhydrite (+1028)
5/29	1830	Drlg.
5/30	2350	Drlg.
6/1	2985	Drlg. Depth

DST #1 - 2956-85' - Op 30", wk. blow for

Date	Depth	
		692997
	17" &	died, Rec. 15' mud, BHP
	616-432#	, FP 54-62#
6/2	3175	Drlg.
	2773	Topeka (=860)
	3129	Brown Line (-1216)
	3141	Lansing (-1228)
6/3	3365	Drlg.
	3393	Arbuckle (-1480)
6/4	3410	R.T.D.
	DST #2 - 3395-3410'	- Op 1 hr., good blow,
		throughout, Rec. 360' wtr.,
	BHP 1047-917#	, FP 82-162#
		D & A 6/4/64